

Mercy Corps - Gadarif State Office		
STABLE Project BHA	Project No:33602	
Bills of Quantities for Mobile Hand wash facility (For One Unit)		
Project name:	Hand wash facility for market in Alfaw Locality (11 Units)	
Project Location:	alfaw / Alfaw Locality	
	GPS:	N E

Item	Description	Unit	Quantity	Unit Rate	Total amount
1	Hand wash facilities:				
1.1	Supply & erect 250 L capacity, plastic cylindrical storage water tank (Tiga), mounted on a 0.8 meters high steel tower with two steel sinks plus two 1/2 inch taps (one in each side) and connect to 20 liters waste water container under the sinks based on design. connect the waste water container with 5 meters hose away from mobile handwash facility. The price is include of all necessary fittings, valves, connection and piping, all according to technical specifications and the directions of the Engineer.	pcs	1		
1.2	Steel tower for water tank				
	Supply, install and welding a square water tank tower width 0.9 x 0.9x 0.8 meters dimension made of Steel angle 2"x 2" with according to drawings, specifications and the directions of the Engineer. Plus one coat antirust and three coats of oil paint,	pcs	1		
	The cost in SDG for one mobile handwash				
	Overhead 30 %				
	Total cost in SDG for one unit				
	Total USD				
	Total cost for 11mobile hand washing in SDG				
	Total cost in USD for 11 units				