

Mercy Corps - Gadarif State Office	
STABLE Project BHA	Project No:33602
Bills of Quantities for mobile Hand wash facility	
Project name:	4 hand wash facilities for clinic
Project Location:	Komour Basheir Area - Alrahad Locality - Gedaref State
	GPS N 13° 11' 1.428" E 34° 51' 25.062"

Item	Description	Unit	Quantity	Unit Rate	Total amount
1	Water Tank:				
1.1	Supply & erect 250 L capacity, plastic cylindrical storage water tank (Tiga), mounted on a 0.8 meters high steel tower with two steel sinks plus two 1/2 inch taps (one in each side) and connect to 20 liters waste water container under the sinks based on design. connect the waste water container with 5 meters hose away from mobile handwash facility. The price is include of all necessary fittings, valves, connection and piping, all according to technical specifications and the directions of the Engineer.	pcs	1		
1.2	Steel tower for water tank				
	Supply, install and welding a square water tank tower width 0.9 x 0.9x 0.8 meters dimension made of Steel angle 2"x 2" with according to drawings, specifications and the directions of the Engineer. Plus one coat antirust and three coats of oil paint,	pcs	1		
	the cost in SDG for one mobile handwash facility				
	Overhaed 30%				
	Total cost in SDG for one mobile handwash				
	Total in USD for one unit				
	Total cost for 4 units in SDG				
	Total cost in USD for 4 units				