

Corrigendum 01 – RFP 23-UNHCR-SDNELF-SUP-RFP-003

For the Provision of Materials and Construction Works of Facilities for UNHCR in Zalingei, Central Darfur

1. RFP Document

Section CONTENT OF THE FINANCIAL OFFER AND BOQ:

- 1- The details of truss and dimension in all items (4.1)
 - **The dimension about center to center each room +Cantilever 1m all Infront view with back slops**
 - **The truss by steel box (8*4)cm , double 8*8 normal steel like beam .**
- 2- The details of rafter and dimension in all items (4.2)
 - **Steel box (8*4cm) (extensions can fixed or welder over truss beam) spraining each other's 1.5m see the 3D structure.**
- 3- The BTU of AC condition needed item (7.4) in all units under electricity work
 - **Provide and installation Air conditioner (AC) 18,000 BTU -type L.G 220-240V two unit (Made in Korea) high quality must be approval by the UNHCR engineer with outside steel seat holder and all accessories.**
- 4- The thickness of rectangular tube
 - **Thickness will be 1mm**