

## Saferwold's office renovations BoQs

.Se	Description	Unit	QTY	Unit Price	Total Price
1	Supply and construction of one person's abolition point	Each	1		
2	Supply and installation of ceramic handwashing basin	Each	1		
3	Partially demolish 2 interior wall 0.5 meter x 2.5 meter long and review the walls plastering	Sum Lump	1		
	Repaint the interior and exterior				
	Supply and Installation of 4 feet electric lamps	Each	4		
	Supply and installation of 2 aluminium windows replacing the wooden ones	Each	2		
	Supply and installation of 100x120cm window blinds, bamboo type	Each	2		
4	Supply and installation of fabricated iron bungalow 3 meters' diameters mounted on a stand of 3-inch pipes with a height of meters. The work includes fixed iron 2.5 chairs with a fixed iron table + wooden cover (ceiling) + civil works	Each	2		
5	Supply materials and fabrication of 15 x 3.8 meter zinc shelter using American zinc sheets including off white painting of the zinc sheets. in addition to create partitions for two prayers locations (one for male and the other for female)	Sum lum	1		
	Supply and installation of Indian Orient fans (large heart)	Each	3		
6	Supply and installation of 4-feet 100-watt bulbs	Each	4		
	Supply and installation of ceramic handwashing basin	Each	1		

	Relocation of the guards booth from outside the budiling to inside the budding with adjusting the size to 3 x 2.5 x 2.5 meters including supply of additional materials need, relocation of air conditioner to inside , electrical installations of lamps and plugs and supply and installation of 40cm x 40 ..cm ceramic for the booth floor	Sum Lump	1		
7	Replacement of the broken glass in office with framing and noise reduction of glass partition size 4x5 meters	Lum sum	1		
8	Glass partioning (4*1.5) meter to create a room using aluminum frameless 0.6 cm glass dark color which should be two rooms with tampered glass 12mm thickness and aluminum profile 1mm 4x4	Each	2		
9	noiseproof for wooden doors size 1 x meters 2	Each	2		
10	Supply and installation of window blinds	Window	11		
11	Interior walls repainting )wired matte paint(, 2 layers painting including covering of wall scracthes and holes if .any	Square meter	615		
12	Exterior walls repainting )using wired matte paint(, 2 layers painting including covering of wall scracthes and holes if any	Square meter	865		
13	Enhancement of razor wire, apply additional layer of razor wire (Blade type) and add more pillars to strengthen the upper fence	meters	110		
14	Replacement of door locks cylinders	Each	10		