

General Notes Fabrication &

installation of solar system fencing for **BBC water yard:** Provision of materials and construct fencing for solar system made from chain link wire, iron angle 2*2inch, 3mm, with tension member from Iron angle 2*2, 3mm for the corners, supported by tensions wires 3 rows, and provided with foundation and short walling for prevention from flooding, in addition to installation of Corinthian barbed wire on the top of the walling each roll to be stretched for 4m. Installation of security light:

Solar light:

Purchasing of security solar lights 3,000 W, working with remote control charging through solar panel, and installing using G.I pipe 3 Inch length 3m, to be fixed on the ground using plain concrete (30*30*50cm) ratio (1:3:6),

(Cement*Sand*Gravel) then treat with fresh water for 3 days Britimes per day.

Firm Name and Address **Prepared by:** Mohammed Abd Elsalam WASH & Infrastructure Officer

Approved by: John Paul Mugo WASH, Shelter & CCCM Coordinator

Project Name and Address

Sida & SDC Project

Project Sida & SDC 12/4/2025