

REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/006

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA
ANNEX-C FINANCIAL PROPOSAL FORM**

1. UNHCR Registration center elevation in Tunaydbah camp					
ITEM DESCRIPTION		UNIT	QTY REQUIRED (EST)	UNIT PRICE USD	TOTAL PRICE USD
MOBILIZATION					
1.1	Mobilization of labor/machinery/workshop for fixing, fabrication and maintaining of any kind of work such as from works, concrete, steel, carpentry ...etc.	Job	1		
SITE CLEARANCE					
2.1	Clearing the site after completing the whole Job and before handover.	Job	1		
RUBBHALL ELEVATION					
3.1	Excavate required depth for foundation 100X50cm, rate includes disposal of excavation to a selected area/use.	ML	136		
3.2	Supply materials and build brick continues foundation with C/S mortar (1:8) width of wall 40cm, height 150cm	M²	204		
3.3	Supply materials and fill sub base layer of selected materials under floor slab of 40cm, rate includes leveling, watering and compaction by 2 layers 20cm each.	M³	192		
3.4	Supply materials and cast 10cm thick concrete (1:3:6) for ground slab (all blocks) in squares 2x2meter, rates includes all related works.	M²	480		
3.5	Supply materials and plaster walls C/S mortar (1:6) for internal and external walls, rate includes walls edges/corners plaster, windows and doors sills and all related works	M²	68		
WALL FENCE					
4.1	Excavate to the required depth for foundation. 40x40x70cm, The work includes disposal of excavation to an approved area.	M³	8		
4.2	Supply materials and cast foundation blocks 40x40x50cm, concrete (1:3:6), rates includes all related works.	M³	8		
4.3	Supply materials and Install heavy duty steel pipe 8x4cm coloumn with the hight of 2.5m and 0.5m under the ground every 2m, anti rust paint coated and accessories including, rate includes all related works.	PC	100		
4.4	Rectangular steel pipes 3x6cm for fence support grids, The work includes fixing, anti rust paint, fixing on the tie beams using bolts and all necessary accessories.	ML	600		
4.5	Supply materials and fix a pre painted corrugated steel sheets 0.35mm thick (for fence) , rate includes fixing steel gutter, corner caps, fixing on the purlins, trusses drilled nails with washer and all necessary accessories.	M²	500		

Company Name:

Signature:

Date:

Stamp:

REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/006

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA
ANNEX-C FINANCIAL PROPOSAL FORM**

4.6	Supply materials and fabricate heavy duty steel double leaf door size of 400x250 cm, made of 5x10cm steel pipes and frame of heavy steel beam, covered with heavy steel sheets 2 sides, includes 1x2meter internal door leaf, anti-rust paint coated and accessories including locks, rate includes fixing to wall, paint and all related works	LS	1		
4.7	Supply materials and fabricate steel door size of 100x220 cm, made of 4x8cm steel pipes and frame of heavy steel pipe 5x10cm, covered with heavy steel sheets 2 sides, paint coated and accessories including locks, rate includes fixing to wall and all related works	LS	1		
EXTERNAL FLOORS					
5.1	Supply materials and backfill of the compound to ensure flood protection with selected materials height of 30cm, rate includes levelling and compaction.	M ³	590		
2. UNHCR Warehouse Elevation in Tunaydbah camp					
ITEM DESCRIPTION		UNIT	QTY REQUIRED (EST)	UNIT PRICE USD	TOTAL PRICE USD
MOBILIZATION					
1.1	Mobilization of labor/machinery/workshop for fixing, fabrication and maintaining of any kind of work such as from works, concrete, steel, carpentry ...etc.	Job	1		
SITE CLEARANCE					
2.1	Clearing the site after completing the whole Job and before handover.	Job	1		
RUBBHALL ELEVATION					
3.1	Excavate required depth for foundation 100X50cm, rate includes disposal of excavation to a selected area/use.	ML	251		
3.2	Supply materials and build brick continues foundation with C/S mortar (1:8) width of wall 40cm, height 150cm	M ²	380		
3.3	Supply materials and fill sub base layer of selected materials under floor slab of 40cm, rate includes leveling, watering and compaction by 2 layers 20cm each.	M ³	350		
3.4	Supply materials and cast 10cm thick concrete (1:3:6) for ground slab (all blocks) in squares 2x2meter, rates includes all related works.	M ²	874		
3.5	Supply materials and plaster walls C/S mortar (1:6) for internal and external walls, rate includes walls edges/corners plaster, windows and doors sills and all related works	M ²	127		
WALL FENCE					
4.1	Excavate to the required depth for foundation. 40x40x70cm, The work includes disposal of excavation to an approved area.	M ³	5		

Company Name:

Signature:

Date:

Stamp:

REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/006

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA
ANNEX-C FINANCIAL PROPOSAL FORM**

4.2	Supply materials and cast foundation blocks 40x40x50cm, concrete (1:3:6), rates includes all related works.	M ³	11.5		
4.3	Supply materials and Install heavy duty steel pipe 8x4cm coloumn with the hight of 2.5m and 0.5m under the ground every 2m, anti rust paint coated and accessories including, rate includes all related works.	PC	144		
4.4	Rectangular steel pipes 3x6cm for fence support grids, The work includes fixing, anti rust paint, paint, fixing on the tie beams using bolts and all necessary accessories.	ML	864		
4.5	Supply materials and fix a pre painted corrugated steel sheets 0.35mm thick (for fence) , rate includes fixing steel gutter, corner caps, fixing on the purlins, trusses drilled nails with washer and all necessary accessories.	M ²	720		
4.6	Supply materials and fabricate heavy duty steel double leaf door size of 400x250 cm, made of 5x10cm steel pipes and frame of heavy steel beam, covered with heavy steel sheets 2 sides, includes 1x2meter internal door leaf, anti-rust paint coated and accessories including locks, rate includes fixing to wall, paint and all related works	LS	4		
4.7	Supply materials and fabricate steel door size of 100x220 cm, made of 4x8cm steel pipes and frame of heavy steel pipe 5x10cm, covered with heavy steel sheets 2 sides, paint coated and accessories including locks, rate includes fixing to wall and all related works	LS	2		
EXTERNAL FLOORS					
5.1	Supply materials and backfill of the compound to ensure flood protection with selected materials height of 30cm, rate includes levelling and compaction.	M ³	590		
3. UNHCR Registration center in Um Rakoba camp					
ITEM DESCRIPTION		UNIT	QTY REQUIRED (EST)	UNIT PRICE USD	TOTAL PRICE USD
MOBILIZATION					
1.1	Mobilization of labor/machinery/workshop for fixing, fabrication and maintaining of any kind of work such as from works, concrete, steel, carpentry ...etc.	Job	1		
SITE CLEARANCE					
2.1	Clearing the site after completing the whole Job and before handover.	Job	1		
RUBBHALL ELEVATION					
3.1	Excavate required depth for foundation 100X50cm, rate includes disposal of excavation to a selected area/use.	ML	136		
3.2	Supply materials and build brick continues foundation with C/S mortar (1:8) width of wall 40cm, height 150cm	M²	204		

Company Name:

Signature:

Date:

Stamp:

REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/006

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA
ANNEX-C FINANCIAL PROPOSAL FORM**

3.3	Supply materials and fill sub base layer of selected materials under floor slab of 40cm, rate includes leveling, watering and compaction by 2 layers 20cm each.	M ³	192		
3.4	Supply materials and cast 10cm thick concrete (1:3:6) for ground slab (all blocks) in squares 2x2meter, rates includes all related works.	M ²	480		
3.5	Supply materials and plaster walls C/S mortar (1:6) for internal and external walls, rate includes walls edges/corners plaster, windows and doors sills and all related works	M ²	68		
WALL FENCE					
4.1	Excavate to the required depth for foundation. 40x40x70cm, The work includes disposal of excavation to an approved area.	M ³	8		
4.2	Supply materials and cast foundation blocks 40x40x50cm, concrete (1:3:6), rates includes all related works.	M ³	8		
4.3	Supply materials and Install heavy duty steel pipe 8x4cm coloumn with the hight of 2.5m and 0.5m under the ground every 2m, anti rust paint coated and accessories including, rate includes all related works.	PC	100		
4.4	Rectangular steel pipes 3x6cm for fence support grids, The work includes fixing, anti rust paint, painting, fixing on the tie beams using bolts and all necessary accessories.	ML	600		
4.5	Supply materials and fix a pre painted corrugated steel sheets 0.35mm thick (for fence) , rate includes fixing steel gutter, corner caps, fixing on the purlins, trusses drilled nails with washer and all necessary accessories.	M ²	500		
4.6	Supply materials and fabricate heavy duty steel double leaf door size of 400x250 cm, made of 5x10cm steel pipes and frame of heavy steel beam, covered with heavy steel sheets 2 sides, includes 1x2meter internal door leaf, anti-rust paint coated and accessories including locks, rate includes fixing to wall, paint and all related works	LS	1		
4.7	Supply materials and fabricate steel door size of 100x220 cm, made of 4x8cm steel pipes and frame of heavy steel pipe 5x10cm, covered with heavy steel sheets 2 sides, paint coated and accessories including locks, rate includes fixing to wall and all related works	LS	1		
EXTERNAL FLOORS					
5.1	Supply materials and backfill of the compound to ensure flood protection with selected materials height of 30cm, rate includes levelling and compaction.	M ³	590		
4. UNHCR Warehouse Elevation in Um Rakoba camp					
ITEM DESCRIPTION		UNIT	QTY REQUIRED (EST)	UNIT PRICE USD	TOTAL PRICE USD
MOBILIZATION					
1.1	Mobilization of labor/machinery/workshop for fixing, fabrication and maintaining of any kind of work such as from works, concrete, steel, carpentry ...etc.	Job	1		

Company Name:

Signature:

Date:

Stamp:

REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/006

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA
ANNEX-C FINANCIAL PROPOSAL FORM**

SITE CLEARANCE					
2.1	Clearing the site after completing the whole Job and before handover.	Job	1		
RUBBHALL ELEVATION					
3.1	Excavate required depth for foundation 100X50cm, rate includes disposal of excavation to a selected area/use.	ML	68		
3.2	Supply materials and build brick continues foundation with C/S mortar (1:8) width of wall 40cm, height 150cm	M²	102		
3.3	Supply materials and fill sub base layer of selected materials under floor slab of 40cm, rate includes leveling, watering and compaction by 2 layers 20cm each.	M³	96		
3.4	Supply materials and cast 10cm thick concrete (1:3:6) for ground slab (all blocks) in squares 2x2meter, rates includes all related works.	M²	240		
3.5	Supply materials and plaster walls C/S mortar (1:6) for internal and external walls, rate includes walls edges/corners plaster, windows and doors sills and all related works	M²	34		
WALL FENCE					
4.1	Excavate to the required depth for foundation. 40x40x70cm, The work includes disposal of excavation to an approved area.	M³	6		
4.2	Supply materials and cast foundation blocks 40x40x50cm, concrete (1:3:6), rates includes all related works.	M³	4.5		
4.3	Supply materials and Install heavy duty steel pipe 8x4cm coloumn with the hight of 2.5m and 0.5m under the ground every 2m, anti rust paint coated and accessories including, rate includes all related works.	PC	54		
4.4	Rectangular steel pipes 3x6cm for fence support grids, The work includes fixing, anti rust paint, paint, fixing on the tie beams using bolts and all necessary accessories.	ML	309		
4.5	Supply materials and fix a pre painted corrugated steel sheets 0.35mm thick (for fence) , rate includes fixing steel gutter, corner caps, fixing on the purlins, trusses drilled nails with washer and all necessary accessories.	M²	265		
4.6	Supply materials and fabricate heavy duty steel double leaf door size of 400x250 cm, made of 5x10cm steel pipes and frame of heavy steel beam, covered with heavy steel sheets 2 sides, includes 1x2meter internal door leaf, anti-rust paint coated and accessories including locks, rate includes fixing to wall, paint and all related works	LS	1		
4.7	Supply materials and fabricate steel door size of 100x220 cm, made of 4x8cm steel pipes and frame of heavy steel pipe 5x10cm, covered with heavy steel sheets 2 sides, paint coated and accessories including locks, rate includes fixing to wall and all related works	LS	1		
EXTERNAL FLOORS					
5.1	Supply materials and backfill of the compound to ensure flood protection with selected materials height of 30cm, rate includes levelling and compaction.	M³	140		

Company Name:

Signature:

Date:

Stamp:

REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/006

REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA
ANNEX-C FINANCIAL PROPOSAL FORM

PLEASE NOTE THAT UNIT PRICE/ TOTAL PRICE SHALL BE QUOTED INCLUSIVE OF SUPPLY, DELIVERY, INSTALLATION, TESTING, COMMISSIONING&LABOURING or ANY OTHER MISCELLANEOUS COSTS

TOTAL COST OF THE ALL WORKS (ALL INCLUSIVE OF SUPPLY, DELIVERY, INSTALLATION, TESTING COMMISSIONING AND LABOURING or ANY OTHER MISCELLANEOUS COSTS)	_____ USD
VALIDITY OF THE PROPOSAL (MIN. 90 DAYS)	_____ DAYS

List of Further Documents to be placed in the Financial Envelope

1. Annex - C Financial Proposal Form

*****The technical proposal and financial proposal are to be sent in separate documents and in separate sealed envelopes placed in a bigger envelope. Failure to do so may result in disqualification.***

Company Name:

Signature:

Date:

Stamp: