

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR CONSTRUCTION OF OFFICE, ACCOMMODATION AND REGISTRATION UNITS IN HAMDAYET, TUNAYDBA AND UM RAKUBA  
ANNEX-B BILL OF QUANTITIES**

**OFFICE ACCOMMODATION IN TUNAYDBA**

| No.      | Description  | Unit                 | Qty        |
|----------|--|----------------------|------------|
| <b>1</b> | <b>MOBILIZATION</b>  |                      |            |
| 1.1      | Mobilization of labor/machinery/workshop for fixing, fabrication and maintaining of any kind of work such as from works, concrete, steel, carpentry ...etc.                  | <b>Job</b>           | <b>1</b>   |
| <b>2</b> | <b>SITE CLEARANCE</b>  |                      |            |
| 2.1      | Clearing the site after completing the whole Job and before handover.  | <b>Job</b>           | <b>1</b>   |
| <b>3</b> | <b>NEW BLOCKS (Accommodation, Offices, Kitchen)</b>  |                      |            |
| 3.1      | Excavate required depth for foundation 130X50cm, rate includes disposal of excavation to away or selected area/use.  | <b>ML</b>            | <b>140</b> |
| 3.2      | Supply materials and fill sub base layer of selected materials under foundation wall of 30cm, rate includes leveling, watering and compaction.                               | <b>M<sup>3</sup></b> | <b>21</b>  |
| 3.3      | Supply materials and build brick continues foundation with C/S mortar (1:8) width of wall 40cm, height 100cm   | <b>M<sup>2</sup></b> | <b>140</b> |
| 3.4      | Supply materials and cast reinforced concrete (1:2:4) with 6Ø16mm steel bars for continues foundation 35x30cm, rate to include form works, steel works and all related works | <b>M<sup>3</sup></b> | <b>15</b>  |
| 3.5      | Supply materials and build brick walls of blocks with C/S mortar (1:8) width of 30cm, including parapet when required, rate to include all related works                     | <b>M<sup>2</sup></b> | <b>560</b> |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|      |   |                      |             |
|------|---|----------------------|-------------|
| 3.6  | Supply materials and cast reinforced concrete (1:2:4) with 4Ø12mm steel bars for tie beams 30x20cm, rate to include form works, steel works and all related works   | <b>M<sup>3</sup></b> | <b>8.4</b>  |
| 3.7  | Supply materials and cast reinforced concrete (1:2:4) with 4Ø12mm steel bars for ring beams 30x20cm (Halls only) rate to include form works, steel works, bolts and all related works   | <b>M<sup>3</sup></b> | <b>8.4</b>  |
| 3.8  | Supply materials and fill sub base layer of selected materials under ground slab of 40cm, rate includes leveling, watering and compaction by 2 layers 20cm each.  | <b>M<sup>3</sup></b> | <b>96</b>   |
| 3.9  | Supply materials and cast 10cm thick concrete (1:3:6) for ground slab (all blocks) in squares 2x2meter, rates includes all related works.   | <b>M<sup>2</sup></b> | <b>240</b>  |
| 3.10 | Supply materials and plaster walls C/S mortar (1:6) for internal and external walls, rate includes walls edges/corners plaster, windows and doors sills and all related works   | <b>M<sup>2</sup></b> | <b>1120</b> |
| 3.11 | Supply materials and fabricate roof trusses structure from , rectangular steel pipes 10X5cm and 8x4cm for roof support grids (for halls) The work includes fixing, anti rust paint, paint, fixing on the tie beams using bolts and all necessary accessories. | <b>M<sup>2</sup></b> | <b>240</b>  |
| 3.12 | Supply materials and fix a pre painted corrugated steel sheets 0.35mm thick (for halls) blue color, rate includes fixing steel gutter, corner caps, fixing on the purlins, trusses drilled nails with washer and all necessary accessories.                   | <b>M<sup>2</sup></b> | <b>240</b>  |
| 3.13 | Supply materials and fix insulation layer (10cm wool) to roof from inside (for all halls) fix to roof by nails and roof rectangular steel pipe.   | <b>M<sup>2</sup></b> | <b>240</b>  |
| 3.14 | Supply and fix (150 X 210) size new solid steel door, locally made, using heavy steel rectangular pipes for door and frame, covered with heavy steel sheet, price to include , fixing with hinges, locking system, paint, etc.                                | <b>No.</b>           | <b>10</b>   |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|          |  |                      |           |
|----------|--|----------------------|-----------|
| 3.15     | Supply material and fabricate (120X120) size new steel windows, locally made, using heavy steel pipes for frame, covered with fiberglass, with horizontal grills made of 4x8cm pipes, price to includes fixing with hinges, locking system, paint, grills etc. | <b>No.</b>           | <b>30</b> |
| 3.16     | Supply materials and Apply washable paint (suitable for interior walls) 2 layers of paint (selected colors) (all blocks), rate includes all related works  | <b>LS</b>            | <b>1</b>  |
| 3.17     | Supply materials and Apply washable paint (suitable for exterior walls) 2 layers of paint (selected colors) (all blocks) rate includes all related works   | <b>LS</b>            | <b>1</b>  |
| <b>5</b> | <b>LATRENES</b>  |                      |           |
| 5.1      | Excavate to the required depth for pit. The work includes disposal of excavation to an approved area.  | <b>M3</b>            | <b>30</b> |
| 5.2      | Supply materials and cast reinforce concrete slab (1:2:4) with bars 12mm @ 15 cm c/c, includes installation of PVC ventilation pipes 4" , rate includes all related works  | <b>M3</b>            | <b>2</b>  |
| 5.4      | Supply materials and build brick continues foundation with cement mortar (1:8). The width of wall 35cm (one &half brick) under the reinforced slab beam, rate includes all related works   | <b>M<sup>2</sup></b> | <b>72</b> |
| 5.5      | Supply materials and build brick for walls of Latrine and the parapet wall with c/s mortar (1:8) The width of wall 20cm (one brick). rate includes all related works   | <b>M<sup>2</sup></b> | <b>43</b> |
| 5.6      | Supply materials and lay plaster of cement mortar (1:6) for internal and external walls and parapet. rate includes all related works   | <b>M<sup>2</sup></b> | <b>86</b> |
| 5.7      | Supply materials and fix a hollow rectangular steel section 60x30mm as a purlin. The work includes pre painting, fixing on the rafters using all necessary plates, bolts, welding and accessories.   | <b>M<sup>2</sup></b> | <b>19</b> |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|          |  |                      |             |
|----------|--|----------------------|-------------|
| 5.8      | Supply and fix a pre painted corrugated steel sheets 0.35mm thick, The work includes, fixing steel gutter, fixing on the purlins using hexagon head, drilled nails with washer and all necessary bars, bolts, and accessories. | <b>M<sup>2</sup></b> | <b>19</b>   |
| 5.9      | Supply material and fabricate steel door of size 80x180cm with frames And rabid steel sheet and accessories including lock, rate includes fixing on wall   | <b>NO.</b>           | <b>8</b>    |
| <b>6</b> | <b>Fence Wall</b>  |                      |             |
| 6.1      | Excavate required depth for foundation 130X50cm, rate includes disposal of excavation to away or selected area/use.  | <b>ML</b>            | <b>160</b>  |
| 6.2      | Supply materials and fill sub base layer of selected materials under foundation wall of 30cm, rate includes leveling, watering and compaction.   | <b>M<sup>3</sup></b> | <b>24</b>   |
| 6.3      | Supply materials and build brick continues foundation with C/S mortar (1:8) width of wall 40cm, height 100cm   | <b>M<sup>2</sup></b> | <b>160</b>  |
| 6.4      | Supply materials and cast reinforced concrete (1:2:4) with 4Ø12mm steel bars for continues foundation 35x30cm, rate to include form works, steel works and all related works   | <b>M<sup>3</sup></b> | <b>17</b>   |
| 6.5      | supply materials and build new brick walls by 3.2 Meter, build with red bricks thick of 30cm, with 1:5 mortar  | <b>M<sup>2</sup></b> | <b>512</b>  |
| 6.6      | supply materials and Plaster of new walls, cement/sand (1:6) mix for new walls, rate to includes materials, labor and all related works  | <b>M<sup>2</sup></b> | <b>1024</b> |
| 6.7      | Supply and Apply paint (suitable for exterior walls) 1 layers of paint (selected colors) for external building elevations  | <b>LS</b>            | <b>1</b>    |
| <b>7</b> | <b>EXTERNAL FLOORS</b>   |                      |             |
| 7.1      | Supply materials and backfill of the compound to ensure flood protection with selected materials height of 30cm, rate includes leveling and compaction.  | <b>M<sup>3</sup></b> | <b>500</b>  |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

**OFFICE ACCOMMODATION IN UM RAKUBA**

| No.      | Description  | Unit                 | Qty        |
|----------|--|----------------------|------------|
| <b>1</b> | <b>MOBILIZATION</b>  |                      |            |
| 1.1      | Mobilization of labor/machinery/workshop for fixing, fabrication and maintaining of any kind of work such as from works, concrete, steel, carpentry ...etc.                  | <b>Job</b>           | <b>1</b>   |
| <b>2</b> | <b>SITE CLEARANCE</b>  |                      |            |
| 2.1      | Clearing the site after completing the whole Job and before handover.  | <b>Job</b>           | <b>1</b>   |
| <b>3</b> | <b>NEW BLOCKS (Accommodation, Offices, Kitchen)</b>  |                      |            |
| 3.1      | Excavate required depth for foundation 130X50cm, rate includes disposal of excavation to away or selected area/use.  | <b>ML</b>            | <b>140</b> |
| 3.3      | Supply materials and build brick continues foundation with C/S mortar (1:8) width of wall 40cm, height 100cm   | <b>M<sup>2</sup></b> | <b>140</b> |
| 3.4      | Supply materials and cast reinforced concrete (1:2:4) with 6Ø16mm steel bars for continues foundation 35x30cm, rate to include form works, steel works and all related works | <b>M<sup>3</sup></b> | <b>15</b>  |
| 3.5      | Supply materials and build brick walls of blocks with C/S mortar (1:8) width of 30cm, including parapet when required, rate to include all related works                     | <b>M<sup>2</sup></b> | <b>560</b> |
| 3.6      | Supply materials and cast reinforced concrete (1:2:4) with 4Ø12mm steel bars for tie beams 30x20cm, rate to include form works, steel works and all related works            | <b>M<sup>3</sup></b> | <b>8.4</b> |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|      |   |            |             |
|------|---|------------|-------------|
| 3.7  | Supply materials and cast reinforced concrete (1:2:4) with 4Ø12mm steel bars for ring beams 30x20cm (Halls only) rate to include form works, steel works, bolts and all related works   | <b>M³</b>  | <b>8.4</b>  |
| 3.8  | Supply materials and fill sub base layer of selected materials under ground slab of 40cm, rate includes leveling, watering and compaction by 2 layers 20cm each.  | <b>M³</b>  | <b>96</b>   |
| 3.9  | Supply materials and cast 10cm thick concrete (1:3:6) for ground slab (all blocks) in squares 2x2meter, rates includes all related works.   | <b>M²</b>  | <b>240</b>  |
| 3.10 | Supply materials and plaster walls C/S mortar (1:6) for internal and external walls, rate includes walls edges/corners plaster, windows and doors sills and all related works   | <b>M²</b>  | <b>1120</b> |
| 3.11 | Supply materials and fabricate roof trusses structure from , rectangular steel pipes 10X5cm and 8x4cm for roof support grids (for halls) The work includes fixing, anti rust paint, paint, fixing on the tie beams using bolts and all necessary accessories. | <b>M²</b>  | <b>240</b>  |
| 3.12 | Supply materials and fix a pre painted corrugated steel sheets 0.35mm thick (for halls) blue color, rate includes fixing steel gutter, corner caps, fixing on the purlins, trusses drilled nails with washer and all necessary accessories.                   | <b>M²</b>  | <b>240</b>  |
| 3.13 | Supply materials and fix insulation layer (10cm wool) to roof from inside (for all halls) fix to roof by nails and roof rectangular steel pipe.   | <b>M²</b>  | <b>240</b>  |
| 3.14 | Supply and fix (150 X 210) size new solid steel door, locally made, using heavy steel rectangular pipes for door and frame, covered with heavy steel sheet, price to include , fixing with hinges, locking system, paint, etc.                                | <b>No.</b> | <b>10</b>   |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|          |  |                      |           |
|----------|--|----------------------|-----------|
| 3.15     | Supply material and fabricate (120X120) size new steel windows, locally made, using heavy steel pipes for frame, covered with fiberglass, with horizontal grills made of 4x8cm pipes, price to includes fixing with hinges, locking system, paint, grills etc. | <b>No.</b>           | <b>30</b> |
| 3.16     | Supply materials and Apply washable paint (suitable for interior walls) 2 layers of paint (selected colors) (all blocks), rate includes all related works  | <b>LS</b>            | <b>1</b>  |
| 3.17     | Supply materials and Apply washable paint (suitable for exterior walls) 2 layers of paint (selected colors) (all blocks) rate includes all related works   | <b>LS</b>            | <b>1</b>  |
| <b>5</b> | <b>LATRENES</b>  |                      |           |
| 5.1      | Excavate to the required depth for pit. The work includes disposal of excavation to an approved area.  | <b>M3</b>            | <b>30</b> |
| 5.2      | Supply materials and cast reinforce concrete slab (1:2:4) with bars 12mm @ 15 cm c/c, includes installation of PVC ventilation pipes 4" , rate includes all related works  | <b>M3</b>            | <b>2</b>  |
| 5.4      | Supply materials and build brick continues foundation with cement mortar (1:8). The width of wall 35cm (one &half brick) under the reinforced slab beam, rate includes all related works   | <b>M<sup>2</sup></b> | <b>72</b> |
| 5.5      | Supply materials and build brick for walls of Latrine and the parapet wall with c/s mortar (1:8) The width of wall 20cm (one brick). rate includes all related works   | <b>M<sup>2</sup></b> | <b>43</b> |
| 5.6      | Supply materials and lay plaster of cement mortar (1:6) for internal and external walls and parapet. rate includes all related works   | <b>M<sup>2</sup></b> | <b>86</b> |
| 5.7      | Supply materials and fix a hollow rectangular steel section 60x30mm as a purlin. The work includes pre painting, fixing on the rafters using all necessary plates, bolts, welding and accessories.   | <b>M<sup>2</sup></b> | <b>19</b> |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|          |  |                      |             |
|----------|--|----------------------|-------------|
| 5.8      | Supply and fix a pre painted corrugated steel sheets 0.35mm thick, The work includes, fixing steel gutter, fixing on the purlins using hexagon head, drilled nails with washer and all necessary bars, bolts, and accessories. | <b>M<sup>2</sup></b> | <b>19</b>   |
| 5.9      | Supply material and fabricate steel door of size 80x180cm with frames And rabid steel sheet and accessories including lock, rate includes fixing on wall   | <b>NO.</b>           | <b>8</b>    |
| <b>6</b> | <b>Fence Wall</b>  |                      |             |
| 6.1      | Excavate required depth for foundation 130X50cm, rate includes disposal of excavation to away or selected area/use.  | <b>ML</b>            | <b>160</b>  |
| 6.3      | Supply materials and build brick continues foundation with C/S mortar (1:8) width of wall 40cm, height 100cm   | <b>M<sup>2</sup></b> | <b>160</b>  |
| 6.4      | Supply materials and cast reinforced concrete (1:2:4) with 4Ø12mm steel bars for continues foundation 35x30cm, rate to include form works, steel works and all related works   | <b>M<sup>3</sup></b> | <b>17</b>   |
| 6.5      | supply materials and build new brick walls by 3.2 Meter, build with red bricks thick of 30cm, with 1:5 mortar  | <b>M<sup>2</sup></b> | <b>512</b>  |
| 6.6      | supply materials and Plaster of new walls, cement/sand (1:6) mix for new walls, rate to includes materials, labor and all related works  | <b>M<sup>2</sup></b> | <b>1024</b> |
| 6.7      | Supply and Apply paint (suitable for exterior walls) 1 layers of paint (selected colors) for external building elevations  | <b>LS</b>            | <b>1</b>    |
| <b>7</b> | <b>EXTERNAL FLOORS</b>   |                      |             |
| 7.1      | Supply materials and backfill of the compound to ensure flood protection with selected materials height of 30cm, rate includes leveling and compaction.  | <b>M<sup>3</sup></b> | <b>500</b>  |

Company Name:

Signature:

Date:

Stamp:



**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

**RECEPTION CENTRE IN HAMDAYET**

| No.      | Description  | Unit                 | Qty        |
|----------|--|----------------------|------------|
| <b>1</b> | <b>MOBILIZATION</b>  |                      |            |
| 1.1      | Mobilization of labor/machinery/workshop for fixing, fabrication and maintaining of any kind of work such as from works, concrete, steel, carpentry ...etc.                  | <b>Job</b>           | <b>1</b>   |
| <b>2</b> | <b>SITE CLEARANCE</b>  |                      |            |
| 2.1      | Clearing the site after completing the whole Job and before handover.  | <b>Job</b>           | <b>1</b>   |
| <b>3</b> | <b>NEW BLOCKS (Two halls 8x5m)</b>   |                      |            |
| 3.1      | Excavate required depth for foundation 130X50cm, rate includes disposal of excavation to away or selected area/use.  | <b>ML</b>            | <b>52</b>  |
| 3.2      | Supply materials and fill sub base layer of selected materials under foundation wall of 30cm, rate includes leveling, watering and compaction.                               | <b>M<sup>3</sup></b> | <b>7.8</b> |
| 3.3      | Supply materials and build brick continues foundation with C/S mortar (1:8) width of wall 40cm, height 100cm   | <b>M<sup>2</sup></b> | <b>52</b>  |
| 3.4      | Supply materials and cast reinforced concrete (1:2:4) with 6Ø16mm steel bars for continues foundation 35x30cm, rate to include form works, steel works and all related works | <b>M<sup>3</sup></b> | <b>5</b>   |
| 3.5      | Supply materials and build brick walls of blocks with C/S mortar (1:8) width of 30cm, including parapet when required, rate to include all related works                     | <b>M<sup>2</sup></b> | <b>208</b> |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|      |   |                      |             |
|------|---|----------------------|-------------|
| 3.6  | Supply materials and cast reinforced concrete (1:2:4) with 4Ø12mm steel bars for tie beams 30x20cm, rate to include form works, steel works and all related works   | <b>M<sup>3</sup></b> | <b>3.12</b> |
| 3.7  | Supply materials and cast reinforced concrete (1:2:4) with 4Ø12mm steel bars for ring beams 30x20cm (Halls only) rate to include form works, steel works, bolts and all related works   | <b>M<sup>3</sup></b> | <b>3.12</b> |
| 3.8  | Supply materials and fill sub base layer of selected materials under ground slab of 40cm, rate includes leveling, watering and compaction by 2 layers 20cm each.  | <b>M<sup>3</sup></b> | <b>32</b>   |
| 3.9  | Supply materials and cast 10cm thick concrete (1:3:6) for ground slab (all blocks) in squares 2x2meter, rates includes all related works.   | <b>M<sup>2</sup></b> | <b>80</b>   |
| 3.10 | Supply materials and plaster walls C/S mortar (1:6) for internal and external walls, rate includes walls edges/corners plaster, windows and doors sills and all related works   | <b>M<sup>2</sup></b> | <b>416</b>  |
| 3.11 | Supply materials and fabricate roof trusses structure from steel beams I sections, T sections, rectangular steel pipes 10X5cm and 8x4cm for roof support grids (for halls) The work includes fixing, anti rust paint, paint, fixing on the tie beams using bolts and all necessary accessories. | <b>M<sup>2</sup></b> | <b>80</b>   |
| 3.12 | Supply materials and fix a pre painted corrugated steel sheets 0.35mm thick (for halls) blue color, rate includes fixing steel gutter, corner caps, fixing on the purlins, trusses drilled nails with washer and all necessary accessories.   | <b>M<sup>2</sup></b> | <b>80</b>   |
| 3.13 | Supply materials and fix insulation layer (10cm wool) to roof from inside (for all halls) fix to roof by nails and roof rectangular steel pipe.   | <b>M<sup>2</sup></b> | <b>80</b>   |
| 3.14 | Supply and fix (150 X 210) size new solid steel door, locally made, using heavy steel rectangular pipes for door and frame, covered with heavy steel sheet, price to include , fixing with hinges, locking system, paint, etc.  | <b>No.</b>           | <b>4</b>    |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|          |  |                      |           |
|----------|--|----------------------|-----------|
| 3.15     | Supply material and fabricate (120X120) size new steel windows, locally made, using heavy steel pipes for frame, covered with fiberglass, with horizontal grills made of 4x8cm pipes, price to includes fixing with hinges, locking system, paint, grills etc. | <b>No.</b>           | <b>12</b> |
| 3.16     | Supply materials and Apply washable paint (suitable for interior walls) 2 layers of paint (selected colors) (all blocks), rate includes all related works  | <b>LS</b>            | <b>1</b>  |
| 3.17     | Supply materials and Apply washable paint (suitable for exterior walls) 2 layers of paint (selected colors) (all blocks) rate includes all related works   | <b>LS</b>            | <b>1</b>  |
| <b>4</b> | <b>LATRENES</b>  |                      |           |
| 4.1      | Excavate to the required depth for pit. The work includes disposal of excavation to an approved area.  | <b>M3</b>            | <b>30</b> |
| 4.2      | Supply materials and cast reinforce concrete slab (1:2:4) with bars 12mm @ 15 cm c/c, includes installation of PVC ventilation pipes 4" , rate includes all related works  | <b>M3</b>            | <b>2</b>  |
| 4.3      | Supply materials and build brick continues foundation with cement mortar (1:8). The width of wall 35cm (one &half brick) under the reinforced slab beam, rate includes all related works   | <b>M<sup>2</sup></b> | <b>72</b> |
| 4.4      | Supply materials and build brick for walls of Latrine and the parapet wall with c/s mortar (1:8) The width of wall 20cm (one brick). rate includes all related works   | <b>M<sup>2</sup></b> | <b>43</b> |
| 4.5      | Supply materials and lay plaster of cement mortar (1:6) for internal and external walls and parapet. rate includes all related works   | <b>M<sup>2</sup></b> | <b>86</b> |
| 4.6      | Supply materials and fix a hollow rectangular steel section 60x30mm as a purlin. The work includes pre painting, fixing on the rafters using all necessary plates, bolts, welding and accessories.   | <b>M<sup>2</sup></b> | <b>19</b> |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|     |  |                |    |
|-----|--|----------------|----|
| 4.7 | Supply and fix a pre painted corrugated steel sheets 0.35mm thick, The work includes, fixing steel gutter, fixing on the purlins using hexagon head, drilled nails with washer and all necessary bars, bolts, and accessories. | M <sup>2</sup> | 19 |
| 4.8 | Supply material and fabricate steel door of size 80x180cm with frames And rabid steel sheet and accessories including lock, rate includes fixing on wall   | NO.            | 8  |

**REGISTRATION CENTRE IN UM RAKUBA**

| No.      | Description   | Unit                 | Qty        |
|----------|---|----------------------|------------|
| <b>1</b> | <b>MOBILIZATION</b>   |                      |            |
| 1.1      | Mobilization of labor/machinery/workshop for fixing, fabrication and maintaining of any kind of work such as from works, concrete, steel, carpentry ...etc. | <b>Job</b>           | <b>1</b>   |
| <b>2</b> | <b>SITE CLEARANCE</b>   |                      |            |
| 2.1      | Clearing the site after completing the whole Job and before handover.   | <b>Job</b>           | <b>1</b>   |
| <b>3</b> | <b>NEW BLOCKS (Halls, Offices)</b>  |                      |            |
| 3.1      | Excavate required depth for foundation 130X50cm, rate includes disposal of excavation to away or selected area/use.   | <b>ML</b>            | <b>114</b> |
| 3.2      | Supply materials and build brick continues foundation with C/S mortar (1:8) width of wall 40cm, height 100cm  | <b>M<sup>2</sup></b> | <b>114</b> |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|      |   |                      |             |
|------|---|----------------------|-------------|
| 3.3  | Supply materials and cast reinforced concrete (1:2:4) with 6Ø16mm steel bars for continues foundation 35x30cm, rate to include form works, steel works and all related works  | <b>M<sup>3</sup></b> | <b>12</b>   |
| 3.4  | Supply materials and build brick walls of blocks with C/S mortar (1:8) width of 30cm, including parapet when required, rate to include all related works  | <b>M<sup>2</sup></b> | <b>456</b>  |
| 3.5  | Supply materials and cast reinforced concrete (1:2:4) with 4Ø12mm steel bars for tie beams 30x20cm, rate to include form works, steel works and all related works   | <b>M<sup>3</sup></b> | <b>6.84</b> |
| 3.6  | Supply materials and cast reinforced concrete (1:2:4) with 4Ø12mm steel bars for ring beams 30x20cm (Halls only) rate to include form works, steel works, bolts and all related works   | <b>M<sup>3</sup></b> | <b>6.84</b> |
| 3.7  | Supply materials and fill sub base layer of selected materials under ground slab of 40cm, rate includes leveling, watering and compaction by 2 layers 20cm each.  | <b>M<sup>3</sup></b> | <b>43.2</b> |
| 3.8  | Supply materials and cast 10cm thick concrete (1:3:6) for ground slab (all blocks) in squares 2x2meter, rates includes all related works.   | <b>M<sup>2</sup></b> | <b>108</b>  |
| 3.9  | Supply materials and plaster walls C/S mortar (1:6) for internal and external walls, rate includes walls edges/corners plaster, windows and doors sills and all related works   | <b>M<sup>2</sup></b> | <b>912</b>  |
| 3.10 | Supply materials and fabricate roof trusses structure from , rectangular steel pipes 10X5cm and 8x4cm for roof support grids (for halls) The work includes fixing, anti rust paint, paint, fixing on the tie beams using bolts and all necessary accessories. | <b>M<sup>2</sup></b> | <b>108</b>  |
| 3.11 | Supply materials and fix a pre painted corrugated steel sheets 0.35mm thick (for halls) blue color, rate includes fixing steel gutter, corner caps, fixing on the purlins, trusses drilled nails with washer and all necessary accessories.                   | <b>M<sup>2</sup></b> | <b>108</b>  |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|          |   |                      |            |
|----------|---|----------------------|------------|
| 3. 12    | Supply materials and fix insulation layer (10cm wool) to roof from inside (for all halls) fix to roof by nails and roof rectangular steel pipe.   | <b>M<sup>2</sup></b> | <b>108</b> |
| 3. 13    | Supply and fix (150 X 210) size new solid steel door, locally made, using heavy steel rectangular pipes for door and frame, covered with heavy steel sheet, price to include , fixing with hinges, locking system, paint, etc.  | <b>No.</b>           | <b>7</b>   |
| 3. 14    | Supply material and fabricate (120X120) size new steel windows, locally made, using heavy steel pipes for frame, covered with fiberglass, with horizontal grills made of 4x8cm pipes, price to includes fixing with hinges, locking system, paint, grills etc.  | <b>No.</b>           | <b>33</b>  |
| 3. 15    | Supply materials and Apply washable paint (suitable for interior walls) 2 layers of paint (selected colors) (all blocks), rate includes all related works   | <b>M<sup>2</sup></b> | <b>456</b> |
| 3. 16    | Supply materials and Apply washable paint (suitable for exterior walls) 2 layers of paint (selected colors) (all blocks) rate includes all related works  | <b>M<sup>2</sup></b> | <b>456</b> |
| <b>4</b> | <b>STEEL WORKS/SHADES</b>   |                      |            |
| 4. 1     | supply materials and fabricate waiting area steel shade 16X10 meter on frame made of steel rectangular pipes 5x10cm and 4x8cm for grids, on 3" steel pipes 3 Meter height clear, 50 cm in conc. base 1:2:4 (total 3.5M) roof of corrugated steel sheets 0.35mm thick as shown with attached design, complete job with anti rust paint and final paint | <b>LS</b>            | <b>1</b>   |
| 4. 2     | Supply materials and fix insulation layer (10cm wool) to roof from inside (for waiting area) fix to roof by nails and roof rectangular steel pipe.  | <b>M<sup>2</sup></b> | <b>160</b> |
| 4. 3     | supply materials and cast 10cm plain conc. mix 1:3:6 For shade floors in 2X2 Meter squares, rate includes preparation of under conc. and all related works  | <b>M<sup>2</sup></b> | <b>160</b> |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|          |   |                |     |
|----------|---|----------------|-----|
| 4.4      | supply materials and fabricate generator steel shade/cage with 2m door double leaf, size of 2X3meter on frame made of steel rectangular pipes 5x10cm and 4x8cm for grids, covered with steel pipes grills, on 3" steel pipes 2.5Meter height, 50 cm conc. base, roof of corrugated steel sheets 0.35mm thick as shown with attached design, complete job with anti rust paint and final paint | LS             | 1   |
| 4.5      | supply materials and cast 15cm reinforced conc.1:2:4 mix platform for generator with steel bars Ø12mm @ 20cm C/C, rate includes all related works   | M <sup>2</sup> | 12  |
| 4.6      | Supply materials and fabricate heavy duty steel door size of 400x250 cm, made of 5x10cm steel pipes and frame of heavy steel beam, covered with heavy steel sheets 2 sides, includes 1x2meter internal door leaf, anti rust paint coated and accessories including locks, rate includes fixing to wall, paint and all related works   | LS             | 2   |
| <b>5</b> | <b>LATRENES</b>   |                |     |
| 5.1      | Excavate to the required depth for pit. The work includes disposal of excavation to an approved area.   | M3             | 51  |
| 5.2      | Supply materials and cast reinforce concrete slab (1:2:4) with bars 12mm @ 15 cm c/c, includes installation of PVC ventilation pipes 4" , rate includes all related works   | M3             | 5   |
| 5.3      | Supply materials and build brick continues foundation with cement mortar (1:8). The width of wall 35cm (one &half brick) under the reinforced slab beam, rate includes all related works  | M <sup>2</sup> | 72  |
| 5.4      | Supply materials and build brick for walls of Latrine and the parapet wall with c/s mortar (1:8) The width of wall 20cm (one brick). rate includes all related works  | M <sup>2</sup> | 72  |
| 5.5      | Supply materials and lay plaster of cement mortar (1:6) for internal and external walls and parapet. rate includes all related works  | M <sup>2</sup> | 144 |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|          |  |                |        |
|----------|--|----------------|--------|
| 5.6      | Supply materials and fix a hollow rectangular steel section 60x30mm as a purlin. The work includes pre painting, fixing on the rafters using all necessary plates, bolts, welding and accessories.                             | M <sup>2</sup> | 19     |
| 5.7      | Supply and fix a pre painted corrugated steel sheets 0.35mm thick, The work includes, fixing steel gutter, fixing on the purlins using hexagon head, drilled nails with washer and all necessary bars, bolts, and accessories. | M <sup>2</sup> | 19     |
| 5.8      | Supply material and fabricate steel door of size 80x180cm with frames And rabid steel sheet and accessories including lock, rate includes fixing on wall   | NO.            | 12     |
| <b>6</b> | <b>Fence Wall</b>  |                |        |
| 6.1      | Excavate required depth for foundation 130X50cm, rate includes disposal of excavation to away or selected area/use.  | ML             | 166    |
| 6.2      | Supply materials and build brick continues foundation with C/S mortar (1:8) width of wall 40cm, height 100cm   | M <sup>2</sup> | 166    |
| 6.3      | Supply materials and cast reinforced concrete (1:2:4) with 4Ø12mm steel bars for continues foundation 35x30cm, rate to include form works, steel works and all related works   | M <sup>3</sup> | 17     |
| 6.4      | supply materials and build new brick walls by 3.2 Meter, build with red bricks thick of 30cm, with 1:5 mortar  | M <sup>2</sup> | 531.2  |
| 6.5      | supply materials and Plaster of new walls, cement/sand (1:6) mix for new walls, rate to includes materials, labor and all related works  | M <sup>2</sup> | 1062.4 |
| 6.6      | Supply and Apply paint (suitable for exterior walls) 1 layers of paint (selected colors) for external building elevations  | LS             | 1      |
| <b>7</b> | <b>EXTERNAL FLOORS</b>   |                |        |
| 7.1      | Supply materials and backfill of the compound to ensure flood protection with selected materials height of 30cm, rate includes leveling and compaction.  | M <sup>3</sup> | 500    |

**REGISTRATION CENTRE IN TUNAYDBA**

| No. | Description | Unit | Qty |
|-----|-------------|------|-----|
|-----|-------------|------|-----|

Company Name:

Signature:

Date:

Stamp:



**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|          |  |                      |             |
|----------|--|----------------------|-------------|
| <b>1</b> | <b>MOBILIZATION</b>  |                      |             |
| 1.1      | Mobilization of labor/machinery/workshop for fixing, fabrication and maintaining of any kind of work such as from works, concrete, steel, carpentry ...etc.                  | <b>Job</b>           | <b>1</b>    |
| <b>2</b> | <b>SITE CLEARANCE</b>  |                      |             |
| 2.1      | Clearing the site after completing the whole Job and before handover.  | <b>Job</b>           | <b>1</b>    |
| <b>3</b> | <b>NEW BLOCKS (Halls, Offices)</b>   |                      |             |
| 3.1      | Excavate required depth for foundation 130X50cm, rate includes disposal of excavation to away or selected area/use.  | <b>ML</b>            | <b>114</b>  |
| 3.2      | Supply materials and fill sub base layer of selected materials under foundation wall of 30cm, rate includes leveling, watering and compaction.                               | <b>M<sup>3</sup></b> | <b>17.1</b> |
| 3.3      | Supply materials and build brick continues foundation with C/S mortar (1:8) width of wall 40cm, height 100cm   | <b>M<sup>2</sup></b> | <b>114</b>  |
| 3.4      | Supply materials and cast reinforced concrete (1:2:4) with 6Ø16mm steel bars for continues foundation 35x30cm, rate to include form works, steel works and all related works | <b>M<sup>3</sup></b> | <b>12</b>   |
| 3.5      | Supply materials and build brick walls of blocks with C/S mortar (1:8) width of 30cm, including parapet when required, rate to include all related works                     | <b>M<sup>2</sup></b> | <b>456</b>  |
| 3.6      | Supply materials and cast reinforced concrete (1:2:4) with 4Ø12mm steel bars for tie beams 30x20cm, rate to include form works, steel works and all related works            | <b>M<sup>3</sup></b> | <b>6.84</b> |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|      |   |                      |             |
|------|---|----------------------|-------------|
| 3.7  | Supply materials and cast reinforced concrete (1:2:4) with 4Ø12mm steel bars for ring beams 30x20cm (Halls only) rate to include form works, steel works, bolts and all related works   | <b>M<sup>3</sup></b> | <b>6.84</b> |
| 3.8  | Supply materials and fill sub base layer of selected materials under ground slab of 40cm, rate includes leveling, watering and compaction by 2 layers 20cm each.  | <b>M<sup>3</sup></b> | <b>43.2</b> |
| 3.9  | Supply materials and cast 10cm thick concrete (1:3:6) for ground slab (all blocks) in squares 2x2meter, rates includes all related works.   | <b>M<sup>2</sup></b> | <b>108</b>  |
| 3.10 | Supply materials and plaster walls C/S mortar (1:6) for internal and external walls, rate includes walls edges/corners plaster, windows and doors sills and all related works   | <b>M<sup>2</sup></b> | <b>912</b>  |
| 3.11 | Supply materials and fabricate roof trusses structure from , rectangular steel pipes 10X5cm and 8x4cm for roof support grids (for halls) The work includes fixing, anti rust paint, paint, fixing on the tie beams using bolts and all necessary accessories. | <b>M<sup>2</sup></b> | <b>108</b>  |
| 3.12 | Supply materials and fix a pre painted corrugated steel sheets 0.35mm thick (for halls) blue color, rate includes fixing steel gutter, corner caps, fixing on the purlins, trusses drilled nails with washer and all necessary accessories.                   | <b>M<sup>2</sup></b> | <b>108</b>  |
| 3.13 | Supply materials and fix insulation layer (10cm wool) to roof from inside (for all halls) fix to roof by nails and roof rectangular steel pipe.   | <b>M<sup>2</sup></b> | <b>108</b>  |
| 3.14 | Supply and fix (150 X 210) size new solid steel door, locally made, using heavy steel rectangular pipes for door and frame, covered with heavy steel sheet, price to include , fixing with hinges, locking system, paint, etc.                                | <b>No.</b>           | <b>7</b>    |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|          |   |                      |            |
|----------|---|----------------------|------------|
| 3.15     | Supply material and fabricate (120X120) size new steel windows, locally made, using heavy steel pipes for frame, covered with fiberglass, with horizontal grills made of 4x8cm pipes, price to includes fixing with hinges, locking system, paint, grills etc.  | <b>No.</b>           | <b>33</b>  |
| 3.16     | Supply materials and Apply washable paint (suitable for interior walls) 2 layers of paint (selected colors) (all blocks), rate includes all related works   | <b>M<sup>2</sup></b> | <b>456</b> |
| 3.17     | Supply materials and Apply washable paint (suitable for exterior walls) 2 layers of paint (selected colors) (all blocks) rate includes all related works  | <b>M<sup>2</sup></b> | <b>456</b> |
| <b>4</b> | <b>STEEL WORKS/SHADES</b>   |                      |            |
| 4.1      | supply materials and fabricate waiting area steel shade 16X10 meter on frame made of steel rectangular pipes 5x10cm and 4x8cm for grids, on 3" steel pipes 3 Meter height clear, 50 cm in conc. base 1:2:4 (total 3.5M) roof of corrugated steel sheets 0.35mm thick as shown with attached design, complete job with anti rust paint and final paint   | <b>LS</b>            | <b>1</b>   |
| 4.2      | Supply materials and fix insulation layer (10cm wool) to roof from inside (for waiting area) fix to roof by nails and roof rectangular steel pipe.  | <b>M<sup>2</sup></b> | <b>160</b> |
| 4.3      | supply materials and cast 10cm plain conc. mix 1:3:6 For shade floors in 2X2 Meter squares, rate includes preparation of under conc. and all related works  | <b>M<sup>2</sup></b> | <b>160</b> |
| 4.4      | supply materials and fabricate generator steel shade/cage with 2m door double leaf, size of 2X3meter on frame made of steel rectangular pipes 5x10cm and 4x8cm for grids, covered with steel pipes grills, on 3" steel pipes 2.5Meter height, 50 cm conc. base, roof of corrugated steel sheets 0.35mm thick as shown with attached design, complete job with anti rust paint and final paint | <b>LS</b>            | <b>1</b>   |
| 4.5      | supply materials and cast 15cm reinforced conc.1:2:4 mix platform for generator with steel bars $\phi$ 12mm @ 20cm C/C, rate includes all related works   | <b>M<sup>2</sup></b> | <b>12</b>  |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|          |   |                      |            |
|----------|---|----------------------|------------|
| 4.6      | Supply materials and fabricate heavy duty steel door size of 400x250 cm, made of 5x10cm steel pipes and frame of heavy steel beam, covered with heavy steel sheets 2 sides, includes 1x2meter internal door leaf, anti rust paint coated and accessories including locks, rate includes fixing to wall, paint and all related works | <b>LS</b>            | <b>2</b>   |
| <b>5</b> | <b>LATRENES</b>   |                      |            |
| 5.1      | Excavate to the required depth for pit. The work includes disposal of excavation to an approved area.   | <b>M3</b>            | <b>51</b>  |
| 5.2      | Supply materials and cast reinforce concrete slab (1:2:4) with bars 12mm @ 15 cm c/c, includes installation of PVC ventilation pipes 4" , rate includes all related works   | <b>M3</b>            | <b>5</b>   |
| 5.3      | Supply materials and build brick continues foundation with cement mortar (1:8). The width of wall 35cm (one & half brick) under the reinforced slab beam, rate includes all related works   | <b>M<sup>2</sup></b> | <b>72</b>  |
| 5.4      | Supply materials and build brick for walls of Latrine and the parapet wall with c/s mortar (1:8) The width of wall 20cm (one brick). rate includes all related works  | <b>M<sup>2</sup></b> | <b>72</b>  |
| 5.5      | Supply materials and lay plaster of cement mortar (1:6) for internal and external walls and parapet. rate includes all related works  | <b>M<sup>2</sup></b> | <b>144</b> |
| 5.6      | Supply materials and fix a hollow rectangular steel section 60x30mm as a purlin. The work includes pre painting, fixing on the rafters using all necessary plates, bolts, welding and accessories.  | <b>M<sup>2</sup></b> | <b>19</b>  |
| 5.7      | Supply and fix a pre painted corrugated steel sheets 0.35mm thick, The work includes, fixing steel gutter, fixing on the purlins using hexagon head, drilled nails with washer and all necessary bars, bolts, and accessories.  | <b>M<sup>2</sup></b> | <b>19</b>  |

Company Name:

Signature:

Date:

Stamp:

**REQUEST FOR PROPOSAL NO: RFP/HCR/ROK/2021/007**

**REQUEST FOR PROPOSAL FOR THE PROVISION OF FENCING AND ELEVATION WORKS IN TUNAYDBA AND UM RAKUBA  
ANNEX-C FINANCIAL PROPOSAL FORM**

|          |  |                      |               |
|----------|--|----------------------|---------------|
| 5.8      | Supply material and fabricate steel door of size 80x180cm with frames And rabid steel sheet and accessories including lock, rate includes fixing on wall                     | <b>NO.</b>           | <b>12</b>     |
| <b>6</b> | <b>Fence Wall</b>  |                      |               |
| 6.1      | Excavate required depth for foundation 130X50cm, rate includes disposal of excavation to away or selected area/use.  | <b>ML</b>            | <b>166</b>    |
| 6.2      | Supply materials and fill sub base layer of selected materials under foundation wall of 30cm, rate includes leveling, watering and compaction.                               | <b>M<sup>3</sup></b> | <b>24.9</b>   |
| 6.3      | Supply materials and build brick continues foundation with C/S mortar (1:8) width of wall 40cm, height 100cm   | <b>M<sup>2</sup></b> | <b>166</b>    |
| 6.4      | Supply materials and cast reinforced concrete (1:2:4) with 4Ø12mm steel bars for continues foundation 35x30cm, rate to include form works, steel works and all related works | <b>M<sup>3</sup></b> | <b>17</b>     |
| 6.4      | supply materials and build new brick walls by 3.2 Meter, build with red bricks thick of 30cm, with 1:5 mortar  | <b>M<sup>2</sup></b> | <b>531.2</b>  |
| 6.5      | supply materials and Plaster of new walls, cement/sand (1:6) mix for new walls, rate to includes materials, labor and all related works                                      | <b>M<sup>2</sup></b> | <b>1062.4</b> |
| 6.6      | Supply and Apply paint (suitable for exterior walls) 1 layers of paint (selected colors) for external building elevations  | <b>LS</b>            | <b>1</b>      |
| <b>7</b> | <b>EXTERNAL FLOORS</b>   |                      |               |
| 7.1      | Supply materials and backfill of the compound to ensure flood protection with selected materials height of 30cm, rate includes leveling and compaction.                      | <b>M<sup>3</sup></b> | <b>500</b>    |

Company Name:

Signature:

Date:

Stamp: