

	BOQ_5 Soba Shareg Health Facility				
Item No.	Item Description	Unit	Quantity	Unit Cost SDG	Total Cost SDG
1-	Roof Works:				
1,1	Supply and installation of plastic water proof for the whole roof of the facility "429 meter square area"to prevent rain water absorption. With it's all needed accessories.	Job	1		
2-	Plastering Works:				
2,1	Supply and performing internal and external rehabilitation plastering works 10% of the 1403 square meter total area , using cement sand mortar mix 1:6. ,2.5 cm thickness.	Job	1		
3-	Doors and Windows Works:				
3,1	Supply and installation of room's doors lock with handle and key for steel doors, good steel lock brand.	No.	12		
4-	Electric Works:				
4,1	Supply and installation of LED Bulb 25 watt ,with it's base and switch, Alfnar brand. For the rooms and halls	No.	30		
4,2	Supply and installation of Orient Fans, with its all needed accessories.	No.	6		
4,3	Supply and installation of electric socket Alfnar brand with all accessories needed.	No.	18		
5-	Painting Works:				
5,1	Procurement & supply and performing internal painting works,for whole building walls,internal roof using walls silk coating "Talia Hareria", water proof silk paints " Almohandis brand",to the best engineering practice and satisfaction of supervisor engineer.	SM	383		
	Procurement & supply and performing external painting works,for whole building walls using water proof silk paints " Almohandis brand",to the best engineering practice and satisfaction of supervisor engineer.	SM	433		
5,2	supply and performing door and windows painting for 12 doors and 18 windows using Almohandis paints.	Job	1		
5,3	Supply and print SHF, RI logo on the enterance wall, using Almohanidis paint and as per site engineer supervision.	Job	1		

	Total				
--	-------	--	--	--	--