

**BOQ\_8 Dar Alsalam 1 HF General Rehabilitation waiting area**

| Item N | Item Description                                                                                                                                                                                                                                                                                                                | Unit | Quantity | Unit Cost SDG | Total Cost SDG |
|--------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|----------|---------------|----------------|
| 1-     | Excavation of " 0.4 meter length, 0.4 meter width, 0.4 meter depth " pit, for Iron posts of the waiting area .                                                                                                                                                                                                                  | No   | 8        |               |                |
| 2-     | supply installation of steel " 4 inch circular pipe 3.5 meter length", for waiting area posts" Rod" .                                                                                                                                                                                                                           | No   | 8        |               |                |
| 3-     | supply, cast concrete 1:2:4 mix "6 meter length, 4 meter width, 0.3 meter depth " for pits to fix waiting area posts "steel pipe rods".                                                                                                                                                                                         | CM   | 24       |               |                |
| 4-     | Procurement, supply and installtion of internal stands steel pipe" 3*6 CM, 1 meter length 3 meter C/C ( No 2.6 c/c) and to the best engineering practice.52 pipes 1 meters length each.                                                                                                                                         | Job  | 1        |               |                |
| 5-     | Procurement, supply and installation of the waiting area 30 SM for all sidw , using Abouhosan Zink sheets 0.35 mm thinkness to cover area of 30 square meter with its steel rectangular pipes, screws, Barabait building and all accessories needed, "20 feet , 20 meter length, 1 cm width" to the best engineering practice.  | Job  | 1        |               |                |
| 6-     | Procurement, supply and installation of the waiting area 20 SM for all sides , using Abouhosan Zink sheets 0.35 mm thinkness to cover area of 20 square meter with its steel rectangular pipes, screws, Barabait building and all accessories needed, "20 feet , 20 meter length, 1 cm width" to the best engineering practice. | job  | 1        |               |                |
| 7-     | Procurement and performing waiting area painting works, "Almohandis paints brand",to the best engineering practice.                                                                                                                                                                                                             | Job  | 1        |               |                |
| 8-     | Printing logo of RI and Donor on steel sheet "well welded and fixed to waiting area" using paints " Almohandis" as attached RI and SHF Logo.1m*1m dimensions.                                                                                                                                                                   | Job  | 1        |               |                |
|        | <b>Total</b>                                                                                                                                                                                                                                                                                                                    |      |          |               |                |